



**Republic of the Philippines**  
Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
Visayas Avenue, Diiman, Quezon City

May 28, 2018

**SUPPLEMENTAL / BID BULLETIN**  
**No. 2018-10**


This Supplemental Bid Bulletin No. 2018-10 is being issued to advise prospective bidder/s to modify and amend certain item in the Bidding Document and Invitation to Apply and Bid, specifically the form of Bill of Quantities for the supply of labor and materials for repair/rehabilitation / improvement of various BAI facilities:

**ITB #2018-050 Supply of Labor and Materials for the Improvement of Various Facilities** at NBCRDC III, Lot 184, Dalwangan, Malaybalay City

**ITB #2018-051 Supply of Labor and Materials for the Repair / Rehabilitation of Duplex Type Staff House** at Gen. Tiño, Nueva Ecija

Please be guided accordingly.

Approved by:

  
**MARIA FE B. CABULLO, DVM, MSA, MNSA**  
Chair, Bids and Awards Committee

Received by the Bidder/Representative: \_\_\_\_\_  
Date: \_\_\_\_\_

Project Title : Supply of Labor and Materials for the Improvement of Various Facilities  
 Location : NBCRDC III, Lot 184, Dalwangan, Malaybalay City  
 Approved Budget Cost: P 450,000.00  
 Project Duration: 60 Calendar Days

**Lot 1: Improvement of Bull Shed No. 1**

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
1.0	<b>DISMANTLING AND CHIPPING WORKS</b>				
1.1	Dismantling of existing roofing including ridge roll	243.20	m <sup>2</sup>		
1.2	Dismantling of 40% of worn-out wooden framing (rafters, purlins, and fascia board)	98.50	m <sup>2</sup>		
1.3	Chipping of existing column and concrete flooring of additional footings and doors	1.00	lot		
	Sub-total 1.0				
2.0	<b>ARCHITECTURAL / CIVIL WORKS</b>				
2.1	Supply / Installation of 40% of entire roof framing (rafters, blocks, purlins, clates, diagonal bracing and fascia board)	98.50	m <sup>2</sup>		
2.2	Supply / Installation of #24 GI corrugated roofing and plain GI ridge roll painted with metal primer only	246.00	m <sup>2</sup>		
2.3	Supply / Fabrication and installation of additional 50mmø (s40) GI pipe rear railings set on reinforced concrete pedestal footing	1.00	lot		
2.4	Supply / Fabrication and installation of additional 10 sets of 50mmø (s40) GI pipe door frames complete with fabricated hinges and lock	10.00	sets		
	Sub-total 2.0				
	<b>GRAND TOTAL</b>				

*Handwritten signature*

Lot 2: **Improvement of Cattle Pen Nos. 1 to 8**

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
1.0	<b>DISMANTLING AND CHIPPING WORKS</b>				
1.1	Dismantling of 36.00 pcs worn-out 6" x 6" hardwood post including pedestal footing steel strap	36.00	pcs		
1.2	Dismantling of storage worn-out plywood panel, wooden wall studs and wooden ceiling joist	1.00	lot		
1.3	Dismantling of 30% of existing dilapidated roof and worn-out floor opening of door including cleaning	187.00	m <sup>2</sup>		
	Sub-total 1.0				
2.0	<b>ARCHITECTURAL / CIVIL WORKS</b>				
2.1	Supply / Installation of 6" x 6" rough wood post, complete with 1/4" x 2" x 12" steel strap with 5/8" ø bolts with knot and washer on existing pedestal footings	36.00	pcs		
2.2	Supply / Installation of hardiflex wall, wooden ceiling and concrete floor of storage	1.00	lot		
2.3	Supply / Installation of doors and windows of storage	1.00	lot		
2.4	Supply / Installation of 30% roof sheet and roof framing of cattle pens #05 and #06	93.20	m <sup>2</sup>		
2.5	Painting works (painting of storage, wall, door, window and ceiling)	1.00	lot		
	Sub-total 2.0				
	<b>GRAND TOTAL</b>				

*Handwritten signature*