



Republic of the Philippines  
Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
*GaBAI sa Pag-unlad ng Paghahayupan*

July 8, 2020

**SUPPLEMENTAL / BID BULLETIN**  
**No. 2020-01**

This Supplemental Bid Bulletin No. 2020-01 is being issued to advise prospective bidder/s on modifications and amendments on certain items in the Bidding Document, Invitation to Apply and Bid and Terms of Reference, if applicable for the infrastructure projects:

ITB/TOR Specifications	Agreements during Pre-Bid Conference
<b>ITB -2020-017</b> <b>Supply of labor and materials for the rehabilitation of drainage system, water lines, toilets and Septic tank of BAI-APDS, Marulas, Valenzuela City</b> <b>ABC - P 3,500,000.00</b>	
Lot 1 – PR No. LRDD APDS 2020-01-001A – ABC P1,500,000.00 Rehabilitation of toilets and septic tank (Veterinarian Office, Dormitory, Canteen and Project Managers' House)	<b>Project Duration: Sixty (60) calendar days (per lot)</b> <b>Warranty Period: one (1) year after acceptance and completion of the contract (per lot)</b> <b>Attached is the revised Bill of Quantities (BOQ) – per lot</b> <b>Note: Participating bidders are required to inspect the site</b>
Lot 2 – PR No. LRDD APDS 2020-01-002A – ABC P 1,000,000.00 Rehabilitation of drainage system	
Lot 3 – PR No. LRDD APDS 2020-01-003A – ABC P1,000,000.00 Rehabilitation of Water Lines	

Please be guided accordingly.

Received: \_\_\_\_\_  
Bidder/Representative

Date : \_\_\_\_\_

  
**FLORENCE D. SILVANO, DVM, PhD**  
BAC Chair- Infrastructure

*"A food-secure Philippines with prosperous farmers and fisherfolk"*



Republic of the Philippines  
 Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
 Visayas Avenue, Diliman, Quezon City

Project : REHABILITATION OF COLD WATER DISTRIBUTION SYSTEM  
 Location : APDC, Marulas, Valenzuela City  
 Subject : Bill of Quantities

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
<b>I.</b>	<b><u>GENERAL REQUIREMENTS</u></b>				
1.0	Provision of tarpaulin	64.00	ft <sup>2</sup>		
2.0	Clean-up, hauling and disposal of debris	1.00	lot		
	<b>Sub-Total - General Requirements</b>				
<b>II.</b>	<b><u>ARCHITECTURAL &amp; CIVIL WORKS</u></b>				
<b>1.0</b>	<b>Demolition/Removal Works</b>				
1.1	Removal of water line, sanitary line, plumbing fixtures and rough-ins	1.00	lot		
1.2	Removal of floor and wall finish	1.00	lot		
1.3	Concrete chipping	330.55	l.m.		
<b>2.0</b>	<b>Concrete Works</b>				
2.1	Restoration of damaged areas	1.00	lot		
<b>3.0</b>	<b>Finishes</b>				
	Tileworks				
	Supply and installation including necessary surface preparation				
3.1	Floor Finishes				
3.1.1	300mm x 300mm x 10mm thk homogenous floor tiles, non-skid @ Project Manager Office	3.00	m <sup>2</sup>		
3.1.2	300mm x 300mm x 10mm thk homogenous floor tiles, non-skid @ Veterinarian Office	9.20	m <sup>2</sup>		
3.1.3	600mm x 600mm x 10mm thk homogenous floor tiles, non-skid @ Canteen	32.80	m <sup>2</sup>		
3.1.4	300mm x 300mm x 10mm thk homogenous floor tiles, non-skid @ Dormitory	26.80	m <sup>2</sup>		
3.1.5	600mm x 600mm x 10mm thk homogenous floor tiles, non-skid @ M&F - Dormitory	34.10	m <sup>2</sup>		
3.2	Wall Finishes				
3.2.1	300mm x 600mm x 10mm thk homogenous wall tiles, polished @ Project Manager Office	11.50	m <sup>2</sup>		
3.2.2	300mm x 600mm x 10mm thk homogenous wall tiles, polished @ Veterinarian Office	26.55	m <sup>2</sup>		
3.2.3	300mm x 600mm x 10mm thk homogenous wall tiles, polished @ Canteen	74.25	m <sup>2</sup>		
3.2.4	300mm x 600mm x 10mm thk homogenous wall tiles, polished @ Dormitory	98.05	m <sup>2</sup>		
	<b>Sub-Total - Architectural &amp; Civil Works</b>				



Republic of the Philippines  
 Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
 Visayas Avenue, Diliman, Quezon City

**Project** : REHABILITATION OF COLD WATER DISTRIBUTION SYSTEM  
**Location** : APDC, Marulas, Valenzuela City  
**Subject** : Bill of Quantities

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
<b>III.</b>	<b>PLUMBING WORKS</b>				
1.0	Supply and installation of water line				
1.1	Project Manager Office	13.00	l.m.		
1.2	Veterinarian Office	13.70	l.m.		
1.3	Canteen	30.00	l.m.		
1.4	Dormitory	170.00	l.m.		
2.0	Supply and installation of sanitary line				
2.1	Project Manager Office	16.00	l.m.		
2.2	Veterinarian Office	24.00	l.m.		
2.3	Canteen	44.85	l.m.		
2.4	Dormitory	197.00	l.m.		
3.0	Supply and installation of plumbing fixtures and accessories	1.00	lot		
4.0	Construction of septic tank/vault including excavation and backfilling				
4.1	2.30m(W) x 2.70m(L) x 1.80m(D) @ Canteen	1.00	unit		
4.2	1.80m(W) x 3.30m(L) x 1.80m(D) @ Dormitory	1.00	unit		
4.3	1.80m(W) x 1.80m(L) x 1.35m(D) @ Dormitory	1.00	unit		
	<b>Sub-Total - Plumbing Works</b>				
<b>GRAND TOTAL COST</b>				<b>Php</b>	<b>1,500,000.00</b>



Republic of the Philippines  
 Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
 Visayas Avenue, Diliman, Quezon City

Project : **REHABILITATION OF DRAINAGE SYSTEM**  
 Location : APDC, Marulas, Valenzuela City  
 Subject : **Bill of Quantities**

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
<b>I.</b>	<b>GENERAL REQUIREMENTS</b>				
1.0	Provision of tarpaulin	64.00	ft <sup>2</sup>		
2.0	Health, safety requirements and signage's	1.00	lot		
3.0	Clean-up, hauling and disposal of debris	1.00	lot		
	<b>Sub-Total - General Requirements</b>				
<b>II.</b>	<b>CIVIL WORKS</b>				
<b>1.0</b>	<b>Demolition/Removal Works</b>				
1.1	Cutting of PCCP	50.00	l.m.		
1.2	Demolition of PCCP and sidewalk	140.00	m <sup>2</sup>		
<b>2.0</b>	<b>Concrete Works</b> (3000 psi @ 28 days including gravel bedding, backfilling, compaction and formworks)				
2.1	Concrete Sidewalk	121.55	m <sup>2</sup>		
2.2	Curbs and gutter	101.30	l.m.		
2.3	Restoration of damaged PCCP	18.80	m <sup>2</sup>		
<b>3.0</b>	<b>Masonry Works</b>				
3.1	Construction of manhole including excavation and backfilling	7.00	units		
<b>4.0</b>	<b>Drainage Works</b>				
4.1	Supply and installation of 0.60mmØ x 1.0m RCCP including excavation, backfilling and gravel bedding	119.00	l.m.		
4.2	Supply and installation of 0.30m x 1.0m steel grating	6.00	sets		
	<b>Sub-Total - Civil Works</b>				
<b>GRAND TOTAL COST</b>				<b>Php</b>	<b>1,000,000.00</b>



Republic of the Philippines  
 Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
 Visayas Avenue, Diliman, Quezon City

Project : REHABILITATION OF WATERLINE  
 Location : BAI-APDC, Marulas, Valenzuela City  
 Subject : Bill of Quantities

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
<b>I</b>	<b><u>GENERAL REQUIREMENTS</u></b>				
1.0	Mobilization/Demobilization (includes electricity and water consumption)	1.00	lot		
2.0	Provision of tarpaulin	64.00	ft <sup>2</sup>		
3.0	Health, safety requirements and signage's	1.00	lot		
4.0	Construction of temporary facility	1.00	lot		
5.0	Clean-up, hauling & disposal of excavated materials	1.00	lot		
	<b>Sub-Total - General Requirements</b>				
<b>II</b>	<b><u>CIVIL WORKS</u></b>				
<b>1.0</b>	<b>Earthworks</b>				
1.1	Excavation	105.20	m <sup>3</sup>		
1.2	Backfill and compaction	121.95	m <sup>3</sup>		
<b>2.0</b>	<b>Demolition/Removal Works</b>				
2.1	Cutting of PCCP	120.50	l.m.		
2.2	Demolition of PCCP	48.20	m <sup>2</sup>		
<b>3.0</b>	<b>Masonry Works</b>				
3.1	Construction of service chamber box	13.00	units		
<b>4.0</b>	<b>Surface Restoration</b>				
4.1	Concrete (fc'=3000psi)	48.20	m <sup>2</sup>		
	<b>Sub-Total - Civil Works</b>				
<b>III</b>	<b><u>PLUMBING WORKS</u></b>				
<b>1.0</b>	<b>Pipe Lines (PN 20)</b>				
1.1	2"Ø PPR pipe	421.70	l.m.		
1.2	1"Ø PPR pipe	14.00	l.m.		
<b>2.0</b>	<b>PPR fittings and accessories including service connections</b>				
		1.00	lot		
	<b>Sub-Total - Plumbing Works</b>				
<b>GRAND TOTAL COST</b>				<b>Php</b>	<b>1,000,000.00</b>