



**Republic of the Philippines**  
Department of Agriculture  
**BUREAU OF ANIMAL INDUSTRY**  
Visayas Avenue, Diiman, Quezon City

May 28, 2018

**SUPPLEMENTAL / BID BULLETIN**  
**No. 2018-10**


This Supplemental Bid Bulletin No. 2018-10 is being issued to advise prospective bidder/s to modify and amend certain item in the Bidding Document and Invitation to Apply and Bid, specifically the form of Bill of Quantities for the supply of labor and materials for repair/rehabilitation / improvement of various BAI facilities:

**ITB #2018-050 Supply of Labor and Materials for the Improvement of Various Facilities** at NBCRDC III, Lot 184, Dalwangan, Malaybalay City

**ITB #2018-051 Supply of Labor and Materials for the Repair / Rehabilitation of Duplex Type Staff House** at Gen. Tiño, Nueva Ecija

Please be guided accordingly.

Approved by:

  
**MARIA FE B. CABULLO, DVM, MSA, MNSA**  
Chair, Bids and Awards Committee

Received by the Bidder/Representative: \_\_\_\_\_  
Date: \_\_\_\_\_

Project Title : Supply of Labor and Materials for the Improvement of Various Facilities  
 Location : NBCRDC III, Lot 184, Dalwangan, Malaybalay City  
 Approved Budget Cost: P 450,000.00  
 Project Duration: 60 Calendar Days

**Lot 1: Improvement of Bull Shed No. 1**

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
<b>1.0</b>	<b>DISMANTLING AND CHIPPING WORKS</b>				
1.1	Dismantling of existing roofing including ridge roll	243.20	m <sup>2</sup>		
1.2	Dismantling of 40% of worn-out wooden framing (rafters, purlins, and fascia board)	98.50	m <sup>2</sup>		
1.3	Chipping of existing column and concrete flooring of additional footings and doors	1.00	lot		
	Sub-total 1.0				
<b>2.0</b>	<b>ARCHITECTURAL / CIVIL WORKS</b>				
2.1	Supply / Installation of 40% of entire roof framing (rafters, blocks, purlins, clates, diagonal bracing and fascia board)	98.50	m <sup>2</sup>		
2.2	Supply / Installation of #24 GI corrugated roofing and plain GI ridge roll painted with metal primer only	246.00	m <sup>2</sup>		
2.3	Supply / Fabrication and installation of additional 50mmø (s40) GI pipe rear railings set on reinforced concrete pedestal footing	1.00	lot		
2.4	Supply / Fabrication and installation of additional 10 sets of 50mmø (s40) GI pipe door frames complete with fabricated hinges and lock	10.00	sets		
	Sub-total 2.0				
	<b>GRAND TOTAL</b>				

*Handwritten signature*

Lot 2: **Improvement of Cattle Pen Nos. 1 to 8**

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
1.0	<b>DISMANTLING AND CHIPPING WORKS</b>				
1.1	Dismantling of 36.00 pcs worn-out 6" x 6" hardwood post including pedestal footing steel strap	36.00	pcs		
1.2	Dismantling of storage worn-out plywood panel, wooden wall studs and wooden ceiling joist	1.00	lot		
1.3	Dismantling of 30% of existing dilapidated roof and worn-out floor opening of door including cleaning	187.00	m <sup>2</sup>		
	Sub-total 1.0				
2.0	<b>ARCHITECTURAL / CIVIL WORKS</b>				
2.1	Supply / Installation of 6" x 6" rough wood post, complete with 1/4" x 2" x 12" steel strap with 5/8" ø bolts with knot and washer on existing pedestal footings	36.00	pcs		
2.2	Supply / Installation of hardiflex wall, wooden ceiling and concrete floor of storage	1.00	lot		
2.3	Supply / Installation of doors and windows of storage	1.00	lot		
2.4	Supply / Installation of 30% roof sheet and roof framing of cattle pens #05 and #06	93.20	m <sup>2</sup>		
2.5	Painting works (painting of storage, wall, door, window and ceiling)	1.00	lot		
	Sub-total 2.0				
	<b>GRAND TOTAL</b>				

*Handwritten signature*

Lot 3: **Improvement of AI Laboratory**  
 Completion Period: 60 Calendar Days

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
1.0	<b>REPAIR AND CHIPPING WORKS</b>				
1.1	Cutting and repair of existing 14 pcs door	14.00	pcs		
1.2	Chipping of existing plain cement finish flooring	360.00	m <sup>2</sup>		
1.3	Demolition and chipping of existing wall @ gridline 3 for opening of door including cleaning	3.20	m <sup>2</sup>		
	Sub-total 1.0				
2.0	<b>ARCHITECTURAL / CIVIL WORKS</b>				
2.1	<b>Masonry Works</b>				
2.1.a	Supply / Laying of 100 thk concrete hollow block wit 10mmø reinforced steel bar	19.50	m <sup>2</sup>		
2.1.b	Plastering of newly laid CHB wall including retouch / finishing of existing	39.00	m <sup>2</sup>		
2.2	Supply and installation of 300mm x 300mm unglazed floor tiles on 25mm thk concrete floor topping complete with PVC floor edge tile trim and tile grout	360.00	m <sup>2</sup>		
2.3	Painting of the newly laid CHB wall ib=including retouch and repair of existing affected portion such as concrete, steel, wood	1.00	lot		
	Sub-total 2.0				
	<b>GRAND TOTAL</b>				

*Abubakar*



Project Title : **Supply of Labor and Materials Repair / Rehabilitation of Duplex Type Staff House**

Location : Gen. Tiño, Nueva Ecija

Approved Budget Cost: P 3,000,000.00

Project Duration: 90 Calendar Days

**Bill of Quantities:**

Item #	Work Description	QTY	Unit	Unit Cost	Total
1.0	<b>GENERAL REQUIREMENTS</b>				
1.1	Mobilization / Demobilization	1.00	lot		
1.2	Tarpaulin	1.00	lot		
1.3	Temporary Facility	1.00	lot		
	Sub-total 1.0				
2.0	<b>EARTHWORKS</b>				
2.1	Wall footing excavation	4.65	m <sup>2</sup>		
2.2	Backfill and compaction	3.00	m <sup>2</sup>		
	Sub-total 2.0				
3.0	<b>ARCHITECTURAL / CIVIL WORKS</b>				
3.1	Dismantling / Demolition Works	1.00	lot		
3.2	Reinforcing Works	103.60	kgs		
3.3	Concrete Works	2.00	m <sup>3</sup>		
3.4	Masonry Works				
	3.4.A CHB laying	22.40	m <sup>2</sup>		
	3.4.B Plastering and retouch	63.00	m <sup>2</sup>		
	3.4.C Flooring and Floor Topping	90.00	m <sup>2</sup>		
3.5	Roofing Works				
	3.5.A Roof framing	1.00	lot		
	3.5.B Roof Sheeting	164.00	m <sup>2</sup>		
3.6	Finishes				
	3.6.A Ceiling	144.00	m <sup>2</sup>		
	3.6.B Floor tiles (Living, dining & bedroom)	82.00	m <sup>2</sup>		
	3.6.C Toilet & bathroom floor & wall tiles	25.00	m <sup>2</sup>		
	3.6.D Kitchen sink tiles	5.90	m <sup>2</sup>		
	3.6.E Bedroom closet	4.00	units		
	3.6.F Kitchen cabinet	2.00	units		
	3.6.G Installation of doors on concrete jamb	1.00	lot		
	3.6.H Installation of steel window	1.00	lot		
3.7	Painting Works				
	3.7.A Existing and additional CHB wall	400.00	m <sup>2</sup>		
	3.7.B Roof framing and purlins	1.00	lot		
	3.7.C Roofing	164.00	m <sup>2</sup>		
	3.7.D Exterior and interior ceiling	144.00	m <sup>2</sup>		
	3.7.E Kitchen cabinet, bedroom cabinet, doors and windows	1.00	lot		
	Sub-total 3.0				
4.0	<b>ELECTRICAL WORKS</b>				
4.1	Conduit and boxes	1.00	lot		
4.2	Service Equipment	2.00	lot		
4.3	Wires and Cables	1.00	lot		
4.4	Electrical devices and Fixtures	1.00	lot		
	Sub-total 4.0				

*Agcatosa*

5.0	<b>ELECTRICAL WORKS</b>				
5.1	Replacement / Installation of sewage and drainage line	1.00	lot		
5.2	Replacement / Installation of cold water line	1.00	lot		
5.3	Replacement / Installation of plumbing fixtures	1.00	lot		
	Sub-total 5.0				
	<b>GRAND TOTAL</b>				

*duroa*