



Republic of the Philippines
 Department of Agriculture
BUREAU OF ANIMAL INDUSTRY
 Visayas Avenue, Diliman, Quezon City

Project : **PROPOSED CONSTRUCTION OF PERIMETER FENCE**
 Location : APDC, Marulas, Valenzuela City
 Subject : **Bill of Quantities**

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
I.	<u>GENERAL REQUIREMENTS</u>				
1.0	Provision of tarpaulin	64.00	ft ²		-
2.0	Clean-up, hauling and disposal of debris	1.00	lot		-
	Sub-Total - General Requirements				-
II	<u>CIVIL/ARCHITECTURAL WORKS</u>				
1.0	Demolition/Dismantling Works				
1.1	Demolition/concrete chipping of slab	26.20	m ²		-
1.2	Removal of cyclone wire perimeter fence	58.70	l.m.		-
2.0	Earthworks				
2.1	Excavation	28.75	m ³		-
2.2	Backfill and compaction	21.60	m ²		-
3.0	Concrete Works				
3.1	Concrete (fc = 3000psi)				
	Footing, column, and tie beam	14.10	m ³		-
3.2	Reinforced Steel Bar (fy = 275Mpa)				
	Footing, column, and tie beam	2,088.52	kgs		-
3.3	Formworks				
	Column	1.00	lot		-
4.0	Masonry Works				
4.1	Concrete hollow block, t = 125mm, including reinforcement and cement mortar grout (non bearing block)	174.80	m ²		-
4.2	Plastering of wall and column(16mm thickness)	394.40	m ²		-



Republic of the Philippines
Department of Agriculture
BUREAU OF ANIMAL INDUSTRY
Visayas Avenue, Diliman, Quezon City

Project : **PROPOSED CONSTRUCTION OF PERIMETER FENCE**
Location : APDC, Marulas, Valenzuela City
Subject : **Bill of Quantities**

Item #	Work Description	Qty.	Unit	Unit Cost	Amount
5.0	Steel/Metal Works				
5.1	Supply and installation of razor wire	94.90	l.m.		-
	Sub-Total - Civil/Architectural Works				-
GRAND TOTAL COST				Php	-